America's Kiver

BEE BRANCH CREEK RESTORATION

CITY OF DUBUQUE, IOWA

ERIC VIETH, P.E. STRAND ASSOCIATES



BEE BRANCH WATERSHED

- Drains to the Bee Branch Creek/Culvert, tributary to the Mississippi
- Approximately 6.5 sq. miles
- Over 50% of Dubuque residents either work or live in the watershed.



Bee Branch Creek Restoration



EXISTING LIMESTONE ARCH CULVERT



Limestone Arch Culvert Constructed in early 1900s





PRESIDENTIAL DISASTER DECLARATIONS IN:

\$70 M in damages





BEE BRANCH WATERSHED





December 1998-2001



BEE BRANCH WATERSHED





Bee Branch Creek Alignment Study Fall 2004



BEE BRANCH WATERSHED

Bee Branch Creek Alignment Study

16th Street Detention Basin



61/151

PROJECT GOALS

Primary - Flood Protection

Secondary – Community Asset

- Aesthetics
- Recreation
- Water Quality



THE BEE BRANCH CREEK DAYLIGHTING SOLUTION IS A.....

"Multiphased, fiscally responsible investment to:

- 1) Mitigate flooding
- 2) Improve water quality
- 3) Stimulate investment
- 4) Enhance quality of life"

• From 2004 to 2009, commercial property values increased by 39% citywide in Dubuque, but they fell by 6% in the flood prone areas.

Daylighting Project will prevent an estimated
\$582 million in damages over the 100-year design life of the project.



WATERSHED PROJECT TIMELINE AND COSTS

Project Timeline



Infrastructure Improvement	Status	Cost
Carter Road Detention Basin	Completed in 2003	\$1,076,315
West 32nd Street Detention Basin	Completed in 2009	\$4,158,589
Lower Bee Branch Creek Restoration	Completed in 2011	\$21,274,685
Historic Millwork District Complete Streets	Completed in 2012	\$7,977,311
Flood Mitigation Gate Replacement	Est. Completion - 2017	\$2,099,000
Upper Bee Branch Creek Restoration	Est. Completion - 2017	\$60,203,636
22nd St. Storm Sewer Capacity Improvements	Est. Completion - 2017	\$3,906,000
North End Storm Sower Capacity Improvements	Est. Completion 2018	\$1,341,000
Bee Branch Creek Railroad Culverts	Est. Completion - 2019	\$18,249,000
Kaufmann Ave. Storm Sewer Capacity Improvements	Est. Completion - 2019	\$11,500,000
Flood Mitigation Maintenance Facility	Est. Completion - 2020	\$5,431,000
Bee Branch Healthy Homes Resiliency Program (Assistance to over 300 homes in the Bee Branch Watershed)	Est. Completion - 2021	\$8,427,665
W. Locust St. Storm Sewer Capacity Improvements	Est. Completion - 2021	\$2,600,000
17th St. Storm Sewer Capacity Improvements	Est. Completion - 2022	\$8,681,000
Water Plant Flood Protection	Est. Completion - 2023	\$4,397,000
Impervious Surface Reduction (240 Green Alleys)	Est. Completion - 2038	\$57,420,000
Total cost, e	\$218,742,201 \$160,000,000	



PUBLIC ENGAGEMENT PROCESS

•	Landscape Design Advisory Committee	Oct 15, 2008
•	Neighborhood Workshop #1	Oct 22/23, 2008
	 Hopes, Desires & Fears of Project 	
	 Visual Preference Survey 	
•	Landscape Design Advisory Committee	Oct 29, 2008
•	Neighborhood Workshop #2	Nov 5/6, 2008
	 Three creek cross section alternatives 	
•	Landscape Design Advisory Committee	Nov 25, 2008
•	Landowner Meeting Opportunity	Dec 9, 2008
	 Three creek cross section alternatives 	



BEE BRANCH CREEK – 1 MILE CORRIDOR



DESIGN PROCESS

In 2009 the focus shifts to complete the final design plans for the . . .

Lower Bee Branch Creek Restoration Project





PHASE I: LOWER BEE BRANCH





CONSTRUCTION

Spring 2010, construction starts on the Lower Bee Branch Creek Restoration Projectwith construction completed in Fall 2011.





PHASE I: LOWER BEE BRANCH





Lower Bee Branch Channel



DOWNSTREAM OF 16TH STREET BRIDGE



UPSTREAM OF 16TH STREET BRIDGE



DOWNSTREAM OF SYCAMORE STREET BRIDGE



16TH STREET DETENTION POND



LOWER BEE BRANCH CREEK RESTORATION





LOWER BEE BRANCH CREEK RESTORATION





LOWER BEE BRANCH – ENHANCED WILDLIFE HABITAT



2014 IOWA DNR FISH ASSESSMENT

- 14 Species of Native Fish
- High Blue Gill Population
- Moderate Bass, Pike, and Perch Population



In 2011 the focus shifts to complete the final design plans for the . . .

Upper Bee Branch Creek Restoration Project



BEE BRANCH CREEK – 1 MILE CORRIDOR





UPPER BEE BRANCH CREEK - OVERALL SITE





UPPER BEE BRANCH CREEK Typical Channel Section



Upper Bee Branch Flyover Rendering





STORMWATER QUALITY ELEMENTS

- PERMEABLE PAVERS
- 3 BIO INFILTRATION BASINS
- 5 NUTRIENT SEPARATING BAFFLE BOXES
- 14 FLOATING TREATMENT ISLANDS



STORMWATER QUALITY – BIOFIELDS (INFILTRATION BASINS)



STORMWATER QUALITY – PERMEABLE PAVERS





STORMWATER QUALITY - GREEN ALLEYS



STORMWATER QUALITY – PERMEABLE PAVERS

STORMWATER QUALITY - TREATMENT DEVICES

STORMWATER QUALITY – NSBB's

- High volume storage
- High flow rates
- Dry state storage

CREEK AERATION FEATURES

CREEK AERATION FEATURES

CREEK AERATION – OUTFALL DAYLIGHTING (CONNECTION TO EXISTING BEE BRANCH CULVERT)

- 2.5 CFS Dry Weather Base Flow
- 4 Foot Elevation Drop from Existing Culvert to New Channel Bottom

CHANNEL CONSTRUCTION - FISH HABITAT

RAILROAD CROSSING- NEXT PHASE

RR CROSSING – TRENCHLESS CULVERTS

- 25 M Estimated Construction Cost
- 6-96" I.D. Steel Culvert Pipes
- Microtunneling or EPB TBM (Earth Pressure Balance Tunnel Boring Machine

RR CROSSING – TRENCHLESS CULVERTS

RR CROSSING – TRENCHLESS CULVERTS

RR CROSSING – LEVEL CONTROL GATE

HINGE CRESTED GATE

SECTION VIEW GATE IN FULLY CLOSED POSITION

LEVEL CONTROL OPERATIONS

NORMAL RIVER ~ NORMAL CHANNEL during Dry Weather

DS HIGH WATER LEVEL – DRY CONDITIONS

PUMPS ON – PUMPED DISCHARGE OF BASE FLOW

LEVEL CONTROL OPERATIONS

NORMAL RIVER ~ NORMAL CHANNEL during Wet Weather

DS FLOOD CONDITIONS (KERPER CLOSED) - EXTREME WET WEATHER 4 PUMPS ON WITH OVERFLOW GATE LOWERS AUTOMATICALLY

RR CROSSING - PEDESTRIAN TUNNEL

RR CROSSING - PEDESTRIAN TUNNEL

TWIN BOX INVESTIGATION

- VISUAL INSPECTION
- GROUND PENETRATING RADAR
- LASER SCANNING

RR CROSSING - PEDESTRIAN TUNNEL

UPPER BEE BRANCH – BEFORE AND AFTER

QUESTIONS?

