Benefits from Stream Restoration Protocols

In a state and and

Øres

Prepared by Joe Caterino May 10, 2018

NATIONAL COVERAGE - LOCAL FOCUS



Founded in Baton Rouge in 2007, RES is the nation's leading provider of ecological and water resource solutions.

RES creates solutions to support economic development and longterm environmental sustainability.

With nearly 400 dedicated individuals across the country -**RES** employees are directly invested in the quality of their work.



WATERSHED POLLUTION DIET

- TMDL Goal to meet reductions by 2025
- 60% of Actions in place by 2017
- Phase III WIP to be developed by 2017
- Nitrogen, Phosphorous, and Sediment
- DE, MD, NY, D.C., PA, WV, and VA



EPA Estimate of Stream and Wetland
Restoration Projects to be Significant Strategy
to Achieve Reductions:
3,096,922 linear feet or 587 restoration
miles 2014 – 2025
92,228 wetland acres

Total Reductions:

25% N 24% P 20% Sediment

Tracking:

Local TMDL Action Plans DEQ Bayfast



STREAM RESTORATION PROTOCOLS

The Chesapeake Bay TMDL has set load reduction goals for TN, TP and TSS for each MS4 permittee in the watershed.

In 2014, an expert panel completed a multiple year effort to establish protocols that MS4 permitees could use to calculate load reductions from stream restoration projects.

The Expert Panel Identified three main protocols for load reduction.

THREE MAIN GOALS FOR LOAD REDUCTION

- PROTOCOL 1 PREVENTED SEDIMENT: This protocol determined the load reduction from reducing bank erosion. The protocol is based on bank erosion hazard index/near bank stress methods. This protocol focus on preventing future loads from the existing channel.
- PROTOCOL 2 DENITRIFICATION: The removal of water column nitrate during baseflow through increasing in-channel de-nitrification. This is the only protocol that solely targets nitrogen, and could be treat-n-load generated upstream of the restoration reach.
- PROTOCOL 3 FLOODPLAIN CONNECTION: This protocol estimates the pollutant removal achieved through storm flows flowing through a vegetated floodplain. This protocol treats pollutant load generated upstream of the restored reach.

PROTOCOL 1 - BEHI



BEHI DATA COLLECTION APPLICATIONS



104R	R	8.0	1.5	2.0	25	65	25			37.57207
Smithwi	ck			Location: Loudoun County, Virg			ginia			
104R				C	bservers:	BS and JA				
	Stream Type:			Valley Type:						
	Stu			udv Bank Height		/ Bankfull Height (C)		BEHI Score (Fig.		. 3-7)
	Study		Bankfull				J(- /			, ,
	Bank	8.00	Height	1.	50	(A)/(B)=	5.33		10.0	
	Height (ft) =	(A)	(ft) =		(B)		(C)			
				Root D	epth / St	udy Bank He	ight (E)			
	Root		Study							
	Depth	2.00	Bank	8.	00	(D)/(A)=	0.25		6.5	
	(ft) =	(D)	Height (ft) :		(A)		(E)			
					Weight	ted Root Den				
			Root							
			Density	25	5%	(F) × (E) =	0.0625		9.3	
			as % =		(F)		(G)			
						Bank Ar	ngle (H)			
						Bank				
						Angle	65		4.4	
					-	as Degrees =	(H)			
				Surface Protection (1)						
						Surface	·			
						Protection	25%		6.5	
					_	as % =	(1)			
	Bank Mate	erial Adjust	ment:							
Bedrock	(Overall Very	y Low BEHI)		>	r	Ban	k Material		•	
Boulders	(Overall Low	v BEHI)		·····	1	A	djustment		U	
Cobble (s	Subtract 10 p	oints it unitori	m medium to la	arge cobble)						
Gravel or	Composite	Matrix (Ad	d 5–10 points	depending		Stratification A	djustment			
6 and (Ad	tage of bank	materiai that i	s composed o	rsand)		Add 5–10 points, d position of unstabl	epending on elavers in		0	
Silt/Clav	(no adjustmer	nt)				relation to bankfull	stage		v	
	(,				L				
Low	Moderate	Hiah	Verv High	Extreme		Adiectiv	e Rating		HIGH	
			113	>			and		36.6	
10 - 19 5	20 - 29 5	30 - 39 5	40 - 45	46 - 50		Tot	al Score			
	20 2010								1	
								- 11.		
							1		MAL.	
									10	ot
							ig H			pt D)
							Ξ			
							BAN	(Bank Angle (H)
				the fire			ģ	1		
			/-		Bankf	ull				
				1410			∃≘Î		− ال	
				AT A			NKF	X	V	
				- da		10000	2 I.		1	
									Star	
								11000	òf	

6 🕖

PROTOCOL 1 – BEHI DATA COLLECTION







7

PROTOCOL 1 - REGIONAL EROSION CURVES

BEHI	NB S		BE HI/NB S	
Very Low	Very Low	0.04	Very LowVery Low	0.04
	Low	0.02	Very LowLow	0.02
	Moderate	0.07	Very LowModerate	0.07
	High	0.43	Very LowHigh	0.43
	Very High	2	Very LowVery High	2
	Extreme	10	Very LowExtreme	10
Low	Very Low	0.04	LowVery Low	0.04
	Low	0.02	LowLow	0.02
	Moderate	0.07	LowModerate	0.07
	High	0.43	LowHigh	0.43
	Very High	2	LowVery High	2
	Extreme	10	LowExtreme	10
Moderate	Very Low	0.04	ModerateVery Low	0.04
	Low	0.12	ModerateLow	0.12
	Moderate	0.3	ModerateModerate	0.3
	High	1.2	ModerateHigh	1.2
	Very High	2	ModerateVery High	2
	Extreme	6	ModerateExtreme	6
High	Very Low	0.25	HighV ery Low	0.25
	Low	0.4	HighLow	0.4
	Moderate	0.62	HighM oderate	0.62
	High	1	HighHigh	1
	Very High	1.7	HighV ery High	1.7
	Extreme	2.65	HighExtreme	2.65
Very High	Very Low	0.25	Very HighVery Low	0.25
	Low	0.4	Very HighLow	0.4
	Moderate	0.62	Very HighModerate	0.62
	High	1	Very HighHigh	1
	Very High	1.7	Very HighVery High	1.7
	Extreme	2.65	Very HighExtreme	2.65
Extreme	Very Low	0.85	ExtremeV ery Low	0.85
	Low	1.25	ExtremeLow	1.25
	Moderate	1.8	ExtremeM oderate	1.8
	High	2.5	ExtremeHigh	2.5
	Very High	3.5	ExtremeV ery High	3.5
	Extreme	5	ExtremeExtreme	5



PROTOCOL 1 - BANK PINS AND BANK STABILITY MODELS

BANK PINS PROVIDE REAL SITE DATA TO VALIDATE MODELING AND REGIONAL CURVE ASSESSMENTS

BANK STABILITY TOE EROSION MODEL (BSTEM)



PROTOCOL 2 – SURFACE WATER AND GROUNDWATER INTERACTION AND CARBON SOURCE PRODUCTION





A. Common River-Floodplain Hydrologic Flowpaths





C. Hyporheic Zone Longitudinal Profile



PROTOCOL 2 – SURFACE WATER AND GROUNDWATER INTERACTION – DAYLIGHTING STREAMS





PROTOCOL 3 – FLOODPLAIN RECONNECTION AND RE-ESTABLISHMENT FO FLOODPLAIN WETLANDS



PROTOCOL 3 – FLOODPLAIN RECONNECTION AND 2-D MODELING





STREAM RESTORATION PROTOCOLS HAVE PLACED GREATER FOCUS ON FUNCTIONAL LIFT

Functional Lift

- Hydrology
 - o Groundwater connection
- Hydraulics
 - Decreasing shear stress
 - o Floodplain connection
 - Increase surface roughness with woody debris and vegetation
- Morphology
 - Stable stream plan form, bed form, and dimension
- Water Quality
 - By reconnecting the surface water and groundwater connection and providing frequen floodplain connection for sediment deposition

Improve Ecology

- $\circ~$ Connection to cooler groundwater
- Woody material for carbon source
- $\circ~$ Riffle bed form for benthic habitat



STREAM RESTORATION PROTOCOLS HAVE PLACED TREMENDOUS VALUE ON RESTORATION OF AGRICULTURAL STREAMS

- High eroded stream banks
- Lack of vegetative buffers
- Direct nutrient impact
- Disconnected floodplains
- Removal of legacy sediments



SUCCESS OF TURN KEY TMDL SOLUTIONS

Key Benefits:

- Applicable to all forms of environmental compensation (wetlands, streams, nutrients, species, habitats, buffers, forests)
- Cost savings through scale and integration
- Fixed pricing and flexible payment schedule
- Reduced administrative and internal overhead costs
- Guaranteed performance bonding
- Customized solution tailored to unique project circumstances



The \$2.13 million project will restore around 6,200 feet of Cattail Creek over the next two years as the county attempts to meet state requirements to tackle stormwater runoff by 2019.



Building a stronger economy and a better environment

Baltimore Baton Rouge Charleston Chicago Columbus Fairfax Houston Lafayette Nashville Oak Hill Odenton Pittsburgh Raleigh Richmond Sea Girt Warrenton