

# Incorporating Ohio Storm Water Requirements Into Your Projects – SWPPPs and BMPs

Jennifer Conroy, PE, CPESC Brian Yates, PE Brian Tornes, PE Kevin Hutchens, PE



# AGENDA

- 1. Clean Water Act/NPDES Framework
- 2. Construction Storm Water Permits
- 3. BMP Case Studies:
  - a. Large Manufacturing Facility, Circleville, Ohio
  - b. Ohio Health Interchange
  - c. Sawmill Parkway Extension
  - d. Lake County Subdivision Project
  - e. Honda of America
  - f. Metro Parks









# **Ohio EPA eBusiness Center**

- Beginning February 1, 2017 General Permit forms are only accessible electronically via the Ohio EPA eBusiness Center. https://ebiz.epa.ohio.gov
- IMPORTANT NOTE: Consultants CANNOT PIN (electronically sign) applications on behalf of their clients. Consultants can COMPLETE the application then DELEGATE it to their client to pin and submit.
- Access electronic versions of the General Permit NOI, NOT, Co-Permittee NOI/NOT through <u>Ohio EPA eBusiness Center</u> account and submit electronically.



**BURGESS &** <sup>4</sup>NIPLE

# **Ohio Construction Storm Water Permit**

#### Ohio Construction Storm Water General Permit

- Statewide
- Big Darby Creek Watershed
- Olentangy River Watershed







# **Ohio Construction Storm Water Permit**

**Ohio Construction Storm Water General Permit** 

- *DRAFT* issued Feb. 9, 2018
- OHC000004 expires April 20, 2018
- OHCD00002 (Big Darby) expired Sept. 30, 2017
- OHCO00002 (Olentangy) expires May 31, 2019



### Applicability General Construction Storm Water Permit

#### One or more acre of disturbance

- Each operator/contractor must seek coverage (co-permittee)
- Off-site borrow pits (one project only) included
- Runoff from contaminated sites not authorized
- Non-impervious, reclamation, mitigation, restoration, and linear projects exempt from post-construction BMPs
- Transportation projects: ODOT L&D Manual

#### All NOIs must be submitted via Ohio EPA eBusiness Center



# **Operator Definition**

"Operator" means any party associated with a construction project that meets either of the following two criteria:

- The party has operational control over construction plans and specifications, including the ability to make modifications to those plans and specifications; or
- 2. The party has day-to-day operational control of those activities at a project which are necessary to ensure compliance with an SWPPP for the site or other permit conditions.
- Operator must 'sign' (submit) NOI and SWPPP (they must have an eBusiness account in order to do this)



### Watershed-Based Requirements

 Big Darby Creek Watershed Construction Storm Water Permit, OHCD00002 (expired 9/30/2017)

 Portions of Olentangy River Construction Storm Water Permit, OHCO00002 (expires 5/31/2019)

These requirements are rolled into the new Construction General Permit (April 2018) for projects in those watersheds



#### **Big Darby Creek Watershed Requirements**

- Submit NOI/SWPPP 45 days (not 21 days) prior to work
- Wait for authorization letter
- Mandatory Riparian Setbacks and Mitigation Requirements
- Groundwater recharge requirements
- Minimum 134 cy/ac sediment basin storage
- 45 mg/I TSS limit and sampling for sediment basins
- No dry detention basins (sites > 5 acres)



#### **Olentangy River Watershed Requirements**

- Submit NOI/SWPPP 45 days (not 21 days) prior to work
- Wait for authorization letter
- Mandatory Riparian Setbacks and Mitigation Requirements



### **Construction Storm Water Pollution Prevention Plans (SWPPPs)**









#### Construction Storm Water Pollution Prevention Plan (SWPPP)

- 1. <u>Site description</u>: cover page, schedule, impervious areas, runoff calculations, soil, receiving stream, etc.
- Site Map(s): existing & proposed contours, construction areas, sediment basin volumes, post-construction BMPs, drainage watersheds, erosion controls, stream crossings, etc.
- 3. <u>Preservation Methods</u>: preserve vegetation, phase construction, buffers
- 4. Erosion Control Practices: stabilization, construction entrances





#### Construction Storm Water Pollution Prevention Plan (SWPPP)

- 5. <u>Runoff control practices</u>: rock checks, slope drains, diversions, velocity dissipation
- <u>Sediment control practices</u>: sediment ponds and traps, sediment barriers, diversions, inlet protection; timing; stabilization
  - Dewater ponds using a skimmer; remove accumulated sediment at 50%
- 7. <u>Post-Construction controls</u>: identify BMPs, design, maintenance plans, WQv calculations, drain times, etc.
- 8. <u>Surface water protection</u>: 401/404 permits; concentrated flow to wetlands



#### Construction Storm Water Pollution Prevention Plan (SWPPP)

- 9. <u>Other controls</u>: waste, concrete washout, off-site traffic tracking, local requirements, trench and gw control, contaminated sediment
- 10. <u>Maintenance</u>: procedures for maintenance of BMPs
- Inspections: every 7 days and within 24 hours after 0.5" storm (monthly if temp. stabilized); "qualified inspection personnel"; inspection report; Summary Record and Certification (keep 3 years)
- 12. <u>Approved state or local plans</u>: ESC approved by local officials keep with SWPPP; certify SWPPP meets MS4 requirements

New general permit requires all SWPPPs to be submitted to Ohio EPA with NOI on eBusiness Center



### **Sediment Pond Design**

- Not just for >10 acre sites
- Dewatering zone: 67 cy/acre of drainage
  - = Volume of water that will slowly discharge from the pond (skimmer)

PLUS

- Sediment settling zone: 37 cy/ disturbed acre
  - = Volume below the level of the pond outlet to allow for sediment accumulation

AND

Release rate: <u>48 hours</u>











# **Erosion Control to minimize sediment control**

Erosion Controls must be installed within 7 days when the site will remain idle for more than 14 days

Examples include:

- Vegetation
- Mulch (i.e., straw or wood chip mulch)
- Matting or Sod
- Ditch Checks
- Riprap
- Geotextiles





### **Sediment Control?**







### **Maintenance of BMPs?**







## **Maintenance of BMPs?**







# **Appropriate Controls?**







# **Stabilization Practices: Hydroseeding**







## **Post-Construction BMPs**

- 1. List of BMPs includes those suitable for small projects (<5 acres)
- 2. Public road projects
  - use ODOT L&D Manual, Vol. II Drainage Design (e.g., vegetated ditches)
- 3. Non-structural BMP options and incentives to reduce WQv and for non-common, low density areas of site
- 4. Local jurisdictions may have more stringent requirements
- 5. Long-term maintenance plan required



## **Post-Construction BMPs**

Table 5a: Extended Detention Practices (24-hr drain)

- Wet extended detention basin
- Constructed extended detention wetland
- Dry extended detention basin (48-hr)
- Permeable pavement- Ext. Det.
- Underground storage Ext. Det.
- Sand and other media filtration Ext. Det.





# **Post-Construction BMPs**

 Table 5b: Infiltration Practices

- Bioretention area/cell (24-hr)
- Infiltration basin (24-hr)
- Infiltration trench (48-hr)
- Permeable pavement Infiltration (48-hr)
- Underground storage —Infiltration (48-hr)





### **Post-Construction Design Considerations**

- Local flood control requirements
- Maintenance
  - Access
  - Pond drain
- Forebays and micropools at inlets and outlets
- Low-Impact design of site
- Resources
  - ODNR "Rainwater and Land Development" Manual
  - City of Columbus "Stormwater Drainage Manual"
  - ODOT L&D Manual, Vol. II
  - Stormwater Manager's Resource Center (www.stormwatercenter.net)



#### Water Quality Volume

The structural post-construction BMP must be sized to treat the water quality volume (WQv) for ALL sites over 1 acre.

 $WQv = \mathbf{Rv} * \mathbf{P} * \mathbf{A}/12$ 

where:

Rv = Volumetric Runoff Coefficient (Rv=0.05+0.9i)P = Precipitation Depth of 0.9-inches

A = Total Contributing Drainage Area (Acres)

WQv = in units of acre-feet



#### Wet Extended Detention Basin

Extended Detention is provided above the wet pool

Extended Detention Volume = 1.0 \* WQv

Permanent Pool = (1.0 \*WQv) + (0.20 \* WQv) forsediment





Source: Ohio EPA

#### Wet Basin Outlet



\*WQV = WATER QUALITY VOLUME



#### **Bioretention**



Runoff that exceeds the WQv bypasses into storm drain system

Storage volume in cell below this inlet = 1.2 \* WQv



#### **BMP Case Studies**

- Large manufacturing facility
- Ohio Health interchange
- Sawmill Parkway Extension
- Lake County subdivision
- Honda Marysville
- Metro Parks









### Large Manufacturing Facility Circleville, Ohio

# Challenge:

- 280 acre site with 1.8 M sf facility (2.2 M sf impervious area)
- Agricultural field with no existing storm sewers
- Over two miles to Scioto River (Scippo Creek Storm Discharge)



Photo: Nov. 2017





### Large Manufacturing Facility Circleville, Ohio

# **Construction Stormwater Solution:**

- Large site challenges
- Multiple Contracts/Phases
- Excavation Dewatering (potential groundwater impacts)





#### **Stormwater Management During Construction**





### Large Manufacturing Facility Circleville, Ohio

### Post Construction Solution:

- Early County buy-in and regular discussions throughout design
- Over 52,000 If storm sewers, 250 catch basins, 180 manholes
- Six detention basins

OHIO STORMWATER

11th Annual

- Eleven Pump stations
- Discharge to nearby Scippo Creek at pre-construction peak flows



Photo: Nov. 2017

### Large Manufacturing Facility Circleville, Ohio

#### BMP Design:

- Worked with European architect on schematic design
  - Significant lengths of trench drain replaced with catch basins
  - Reuse of roof runoff to supplement groundwater source for process water
  - Sand- and gravel-dominated subsurface allowed for incorporation of infiltration trenches in design
- Modeling of 1-year to 25-year design storms in HEC-HMS with and without infiltration
- Risk management decisions to reduce costs for larger design storms
- Redesign of pump stations to reduce costs
- Reroute roof drainage to south ditch to be picked up with storm sewers in subsequent phases of design



#### 2018 OHIO STORMWATER C O N F E R E N C E 11th Annual



11th Annual

# Ohio Health SR 315 Interchange

Storm Water Management

### Challenges:

- Heavily-urbanized area with spatiallydispersed construction
- Restrictions on placement of stormwater control facilities (e.g., ROW, floodplain)
- Coordination with multiple agencies (e.g., Columbus, EPA, ODOT, USACE)
- City of Columbus Stream Corridor Protection Zones, Jurisdictional Streams, City plans for reginal basin





## Ohio Health SR 315 Interchange Storm Water Management

Success Metrics:

- Provide compensatory stormwater quantity control within the regional basin
- Provide stormwater quality control either onsite or compensatory within the regional basin (1.5X GP Requirement)
- Reduce peak water surface elevation in basin by 7.45 ft.
- Reduce peak outflow from regional basin by 39 cfs









### Ohio Health SR 315 Interchange Storm Water Management

#### Solutions:

OHIO STORMWATER

11th Annual

- Redesign of existing regional basin for compensatory stormwater quantity control
- Vegetated swales, filter strips, and existing manufactured systems for stormwater quality control
- Forebays/micropools in regional basin for quality control
- Realignment of on-ramps and roadways



### Ohio Health SR 315 Interchange Storm Water Management

#### Regional Basin:

- Currently provides quantity control (1991 design) but no quality control
- Six inlets total (one stream, one ditch, four storm drains from SR-315)
- Jurisdictional stream (Slyh Run) running through the basin
- Mostly flat area not conducive to vegetated swales (in most locations)





#### Ohio Health SR 315 Interchange Storm Water Management

#### Model Set-up and Results

2018

11th Annual

OHIO STORMWATER





# **Sawmill Parkway Extension**

## Challenge:

- 4 lane divided highway through residential and agricultural areas; original design completed 10 years before construction
- Olentangy River Watershed Permit Area
- While the plans sat, regulations changed and some BMP's were no longer permissible
- Right of way had already been purchased, so an innovative solution was needed





# **Sawmill Parkway Extension**

Solution:

- In-line detention within the footprint of the ditches
- Utilized embankment to impound WQv and spillway to convey larger storms





## Sawmill Parkway Extension Stormwater Design

- 14 extended retention basins
  - Designed to meet the post construction water quality volume (WQv) requirements
  - Ultra flat terrain
  - 2-stage concrete weir vs. catch basin for the outlet structure
  - Easy to inspect/maintain
  - Far more reliable than the catch basin and pipe system











# **Sawmill Parkway Extension**

#### A word of caution about wildlife and plantings

- This project fell victim to migratory birds feeding on the fresh plantings for the retention basins
- A sizeable investment was very soon lost to birds
- Deer and muskrats can also be a problem with fresh plantings
- Use humane deterrents to keep migratory birds
- Work with your landscape architect to select plants that are project appropriate but undesirable to wildlife







#### Two Watersheds Met Causing Damage and Danger





# A Closer Look at the Problem and Solution





- A forebay addresses the 4 outfalls at west end of the pond
- This basin is unique pond bottom is bed rock







Construction















### Honda Marysville Storm Water Pond Enhancements

#### Challenge

- Do the Storm Water Management Ponds meet newer storm water requirements?
- If not, how do we enhance them to meet the new requirements (even though not required)?

#### Solution

- Evaluated the ponds
- Recommended enhancements





### Honda Pond Outfall Enhancement



Before



After



#### HRA Pond – before

#### Challenge:

Pond discharge does not meet 24-hour drain time

Overtops above 2-year storm event







#### HRA Pond – after

#### Solution:

Constructed wetland provides detention time and flood reduction volume





# Columbus and Franklin County Metro Parks: Whittier Peninsula

#### Challenge:

 Revitalize an abandoned industrial center and reduce environmental impacts of storm water discharges.





# Scioto Audubon Metro Park

#### Solution:

 Clean-up under the Voluntary Action Program (VAP) and utilize a variety of storm water BMPs.





### Scioto Audubon Metro Park Rain Gardens

- Small drainage areas
- TSS reduction
- Relatively inexpensive





### Scioto Audubon Metro Park Pervious Pavements

- TSS reduction
- Quantity control







#### Scioto Audubon Metro Park Bioswales

- Suspended Solids
- Organics
- Groundwater Recharge





## Scioto Audubon Metro Park Constructed Wetlands

#### Removes:

- Suspended solids
- Nitrogen
- Phosphorus
- Heavy metals





# **Columbus and Franklin County Metro Parks**

#### Challenge:

Protect sensitive Big Darby Creek Watershed







# Big Darby Creek Metro Park and Prairie Oaks Metro Park Wetlands, Wet Prairies and Wildlife

Solution:

Convert agricultural land to wetlands, wet prairies, savannahs, and pastures to preserve the watershed and attract wildlife.







# **Battelle Darby Creek Nature Center**

 Includes constructed wetlands, bioretention, native vegetation, green roof, and underground detention



OHIO STORMWATER

11th Annual





# Prairie Oaks Metro Park

#### Wet Prairie Restoration Challenge:

- Maintain off-site drainage
- Coordinate with County

#### Solution:

- Convert agricultural land to wet prairies and savanna
- New catch basins and piping for off-site drainage





# **Final Thoughts**

#### Managing storm water can be challenging

- Site constraints
- Local jurisdiction requirements
- Delays in project timing/changing regulatory requirements

#### There are a variety of solutions

- Understand the requirements in the construction permit
- Work with the site conditions
- Coordinate with the Ohio EPA and local jurisdictions early and often







# QUESTIONS?



Jennifer Conroy, PE, CPESC jennifer.conroy@burgessniple.com 614.218.6460



Brian Tornes, PE brian.tornes@burgessniple.com 614.519.9662



Brian Yates, PE brian.yates@burgessniple.com 614.558.2689 Kevin Hutchens, PE kevin.hutchens@burgessniple.com 440.354.9700

BURGESS & NIPLE Engineers Environmental Scientists Planners