

An aerial photograph of a river system. In the upper portion, a large, light-colored, winding structure, likely a dam or a large-scale erosion control project, is visible. The river flows through a lush green forested area. In the lower portion, a bridge crosses the river, and a large industrial or commercial building is situated on the left bank. The overall scene depicts a significant water management project in a natural setting.

Boardman Dam Removal Observations and Lessons Learned

Troy Naperalala, PE

May 11, 2018

AECOM

PROJECT PARTNERS

- U.S. Army Corps of Engineers
- Grand Traverse Band
- City of Traverse City
- Grand Traverse County
- Michigan DEQ
- Michigan DNR
- Michigan Hydro Relicensing Coalition
- Traverse City Light & Power
- U.S. Fish & Wildlife Service
- U.S. Environmental Protection Agency
- Conservation Resource Alliance
- Grand Traverse Conservation District
- Grand Traverse County Road Commission
- Rotary Camps & Services
- Watershed Center, Grand Traverse Bay
- Garfield Twp.

BOARDMAN DAM REMOVAL OBSERVATIONS AND LESSONS

- Project Overview
- Community Interaction
- Change Management
- Engineer Intent vs. Contractor Interpretation
- Recycle/Reuse – opportunities and challenges
- When It Rains, It Pours

BOARDMAN DAM REMOVAL OBSERVATIONS AND LESSONS

- **Project Overview**
- Community Interaction
- Change Management
- Engineer Intent vs. Contractor Interpretation
- Recycle/Reuse – opportunities and challenges
- When It Rains, It Pours



Boardman River Dams



PROJECT OVERVIEW



- 360,000 CYD of material moved
- 11,000 ft. of restored channel
- 400 logs
- 18 months of construction




PROJECT OVERVIEW TOP 10 LIST

- 360,000 CYD of material moved
- 11,000 ft. of restored channel
- 400 logs
- 18 months of construction



PROJECT OVERVIEW TOP 10 LIST

- 14 siphons @ 400 - 700 cfs
- 26 ft. of head
- 1 powerhouse demo
- 1 constructed riffle
- 1 temporary spillway



PROJECT OVERVIEW TOP 10 LIST

- 14 siphons @ 400 - 700 cfs
- 26 ft. of head
- 1 powerhouse demo
- 1 constructed riffle
- 1 temporary spillway



BOARDMAN DAM REMOVAL OBSERVATIONS AND LESSONS

- Project Overview
- **Community Interaction**
 - Public Interaction
 - Turbidity
- Change Management
- Engineer Intent vs. Contractor Interpretation
- Recycle/Reuse – opportunities and challenges
- When it Rains, it Pours

Public Viewing



Public Viewing



Walking & Paddling




Walking & Paddling



Turbidity

RELATIONAL TRENDS OF FRESH WATER FISH ACTIVITY TO TURBIDITY VALUES AND TIME



BOARDMAN DAM REMOVAL OBSERVATIONS AND LESSONS

- Project Overview
- Community Interaction
- **Change Management**
 - Relic Structures
 - Evolving River Conditions
 - Design Flexibility
- Engineer Intent vs. Contractor Interpretation
- Recycle/Reuse – opportunities and challenges

Relic Structures – Cass Bridge



Relic Structures

Corewall




Relic Structures Corewall




Evolving River Conditions




Evolving River Conditions




Evolving River Conditions



Design Flexibility




TO PREVENT SEEPAGE THROUGH THE SEDIMENT PLUG AND WASH OUT OF SEDIMENT, PLACE 2.5 FEET THICK LAYER OF CHANNEL BED MATERIAL (REFER TO STREAMBED CONSTRUCTION SPECIFICATION) ON THE LOWER 8 FEET OF EXCAVATION EMBANKMENT.



TEMPORARY BULKBAG COFFERDAM

NOTE: SAND BAGS TO BE INSTALLED PER MANUFACTURE'S RECOMMENDATIONS. AFTER REMOVAL OF DOWNSTREAM EARTHEN PLUG, REMOVE TOP ROW OF BULK BAGS, STARTING AT CHANNEL CENTERLINE, AT RATE THAT PRODUCES MAXIMUM DRAWDOWN IN IMPOUNDMENT OF HALF FOOT PER HOUR. REPEAT FOR SUBSEQUENT ROWS.

Design Flexibility




Design Flexibility



BOARDMAN DAM REMOVAL OBSERVATIONS AND LESSONS


- Project Overview
- Community Interaction
- Change Management
- **Engineer Intent vs. Contractor Interpretation**
 - Siphon
 - Dewatering and sediment management
- Recycle/Reuse – opportunities and challenges
- When It Rains, It Pours

SIPHON SYSTEM



TEMPORARY SIPHON DEWATERING SYSTEM PLAN

SIPHON SYSTEM










DEWATERING & SEDIMENT MANAGEMENT









DEWATERING & SEDIMENT MANAGEMENT



DEWATERING & SEDIMENT MANAGEMENT



DEWATERING & SEDIMENT MANAGEMENT







BOARDMAN DAM REMOVAL OBSERVATIONS AND LESSONS

- Project Overview
- Community Interaction
- Change Management
- Engineer Intent vs. Contractor Interpretation
- **Recycle/Reuse – opportunities and challenges**
- When it Rains, it Pours

RECYCLE / REUSE



- Tree clearing as part of project

RECYCLE / REUSE



- Numerous large wood installations
- Uses for slash material in LWD
- Mulched or buried a lot of cleared debris

RECYCLE / REUSE



- Vegetation salvage for reestablishing floodplain
- Used in a few designated areas, could have been used more extensively

RECYCLE / REUSE



- Completed reuse

BOARDMAN DAM REMOVAL OBSERVATIONS AND LESSONS

- Project Overview
- Community Interaction
- Change Management
- Engineer Intent vs. Contractor Interpretation
- Recycle/Reuse – opportunities and challenges
- **When It Rains, It Pours**

October 24, 2017, 700 cfs

Peak on 10/25/17 – 900 cfs
10-yr = 1,200 cfs
100-yr = 1,700 cfs







**THERE'S ALWAYS SOMETHING
YOU WEREN'T PLANNING FOR**













QUESTIONS?

