



ODOT's Tait Station Dam Removal: Leveraging Public Partnerships with Watershed Management Goals



May 10, 2019

Ohio Stormwater Conference Sharonville Convention Center Session F1C, Room: 103 Sharonville, Ohio

#### **Presentation Outline**

#### OUTLINE

- Project Background
- Project Need
- ✓ Goals and Objectives
- Project Partnership
- Project Funding and Mitigation
- Design and Permitting
- ✓ Construction
- Monitoring and Performance Evaluation







### Why ODOT Involvement

- ODOT stream mitigation need in the Lower Great Miami Watershed
- Tait Station Dam identified as a candidate for removal
- Cost-benefit analysis showed dam removal costs cheaper than in-lieu fee by >\$500,000.00
- ODOT's full delivery mitigation task order utilized







#### **Project Background**

## Why Tait Station Dam needs to be removed?

- Barrier to aquatic life and recreational boating
- Maintenance liability for Miami Conservancy District (MCD)
- Significant large woody debris disposal and costs
- Public health & safety hazard
- Watershed Action Plan Impairment








#### Project Background

- Tait Station c. 1935 (Dayton Power and Light)
- Dam was constructed to provide cooling water intake source to support power plant production
- Power plant decommissioned in 1983
- Ownership of dam transferred to Miami Conservancy District in 1990
  - o MCD's "Mistake by the Intake"
- Planning and grant applications to remove the dam started in 2014 (MCD)
- Dam no longer provides any beneficial public use.
- Dam does NOT provide any flood control purpose







### **Project Purpose and Need**

- ODOT has stream mitigation need in this watershed (2,678 LF for the BUT-73/177 Improvement Project)
- Tait Station Dam has become a barrier to aquatic and recreational uses of the GMR
- Aquatic and recreations impairments have been noted by numerous public agencies (Ohio EPA, 1995 and 2010)
- Maintenance liability to Miami Conservancy District (MCD, 2015)
- Large Woody Debris disposal and costs have increased
- Public Health and Safety Hazard
  - Recent fatalities on similar low head dams in Hamilton and Miamisburg. Note: These are also in process of being removed









### **Project Goals and Objectives**

#### **Project Goal:**

• To remove the Tait Station Dam and its associated infrastructure such that ecological lift is fully and functionally returned to the GMR within the area of the river channel (formerly) pooled under the influence of the Tait Station Dam.

#### **Project Objectives:**

- Demonstrate that the Project will provide over >2,678 LF of stream mitigation credits to satisfy ODOT's current mitigation need in the Lower GMR Watershed
- Meet or exceed Ohio EPA's use attainment status (WWH) for the GMR within the Project limits
- Improve water quality by reestablishment of riffle/pool complexes within Project limits
- Improve river ecology by rehabilitation of aquatic habitat for macroinvertebrates, fish, and unionid mussel species
- Restore habitat features and riparian buffers, to the degree practicable, by reestablishment of floodplain connectivity and/or adjacent wetlands





### **Project Goals and Objectives**

#### **Project Objectives (Continued):**

- Provide education and outreach opportunities for stakeholders to improve public awareness regarding the value of the GMR and its aquatic resources
- Obviate maintenance needs for Project stakeholders, namely MCD
- Eliminate a clear and present threat to public safety for those who enjoy recreational use of the GMR.
- Protect existing transportation infrastructure and other known utilities near Tait Station Dam





#### Project Partnership –

No one can do it alone!



- ODOT Project Funding, Design, Permitting, Engineering and Construction
- MCD Technical Support, Background Data, Site Access, Funding and Resolutions
- City of Dayton, Department of Water Utility Coordination, Utility Relocation
- DP&L Utility Coordination, Site Access, Transmission Tower Access for webcam
- University of Dayton Monitoring



one source










#### **Potential Mitigation Credits**







### Project Update (September 2018)

- Design Complete (Nov 2017)
- All Permits Received (Dec 2017)
- 9,471 Stream Mitigation Credits received (Jan 2018)
  - ILF Market Value of \$2.46M
    - \$260 / LF (Credit)
  - PRM Total Project Cost is ~\$1.75M
    - o \$185 / LF (Credit)



- Pooled Mitigation Extra Credits > \$500K for State of Ohio
- Construction / Restoration (July 2018) IN PROGESS

Mitigation Project (Credits)	Ohio EPA RM (Start / Stop)	Credit Unit (LF)	Credit Ratio	Credits
Type 1, Activity Level 2 (active work zone)	(77.45 - 77.75)	1,584	1.50 : 1	2,376
Type 1, Activity Level 4 (pool reduction only)	(77.75 - 79.50)	9,460	0.75 : 1	7,095
TOTAL				9,471

Table 1 – Revised Estimated Stream Mitigation Credits





### Permitting and NEPA Compliance

#### **Ecological and Waterway Permitting**

- Corps Section 404 Permit (Dec 2017)
- USFWS Section 7 Coordination (March 2017)
- OHPO Section 106 Coordination (Jan 2016)
- NEPA C-1 Categorical Exclusion (July 2017)
- Floodplain Coordination (March 2017)
- Ohio EPA Contaminated Sediments (Feb 2017)
- Ohio EPA NPDES CGP (May 2018)










Ο





















#### Great Miami River Discharges

**Table 1:** Discharges used within the Tait Station project model (HEC-RAS) and their sources (\*=matches FIS).

		Discharges (cfs)	
	Conceptual <sup>1</sup>	Map Modernization <sup>2</sup>	USGS Gage
<b>Recurrence Interval</b>	(2014)	(2015)	03270500
Annual Mean			2680
Inner berm flow			9,000
1.5 year (bankfull)			22,000
2 year	33,000		
5 year	46,500		
10 year	56,000*	56,000*	
1959 Flood		62,000	
25 year	67,000	64,250	
50 year	78000*	78000*	
100 year	86000*	86000*	
500 year		107,000*	
OPF	120,000	120,000	





#### **HEC-RAS Model**


- Combination of:
- Existing models (FEMA HEC-2),
- Additional field surveys
- Calibrated with
  20 additional
  cross sections
  and a longitudinal
  profile

Figure 2. HEC-RAS profile showing select water surface profiles for the Full Dam and the Dam Removed with Grade Control. Results show that the dam pool extends upstream to near the Third Street Bridge.






OHIO DEPARTMENT OF













#### Creating floodplain benches with stone toe protection
























#### Table 2: Riffle dimensions and ODOT rock type quantities for each section of the riffle


Riffle	L (ft)	W (ft)	Size	d85	d50	Qty (CY)
Glide Stone	14	460	ODOT C	18in	12in	540
Crest Stone	6	460	ODOT B	24in	18in	240
Habitat Enhancement	3	460	ODOT A	30 in	24in	60
Run Stone	76	460	ODOT C	18in	12in	3000
Key Trench	3	460	ODOT C	18in	12in	160
Riffle Dimensions	90	460				4000




OHIO DEPARTMENT OF







#### **Special considerations**





400

800

200



ATT SE

C EL

1.21.2


25


200



#### **Special considerations**

• Scour model suggests very little change between full dam, existing dam and dam removed conditions










#### **Additional Concerns**

- Mussel beds / Mussel salvage
- Changes since original (2016-17) Surveys
- Asbestos
- N&S Railroad
- Legacy DP&L Intake Structures













### Construction Schedule

7				
ID	Task Name	Duration	Start	Finish
1	•	54 days	Mon 8/6/18	Thu 10/18/18
2	•	11 days	Mon 8/6/18	Mon 8/20/18
3	Construction Mobilization &	3 days	Mon 8/6/18	Wed 8/8/18
	Temporary Access	2.1	TI 0/0/40	5:04040
4		2 days	Thu 8/9/18	Fri 8/10/18
5		5 days	Mon 8/13/18	
6	,	1 day		Mon 8/20/18
7	•	31 days	Tue 8/21/18	Tue 10/2/18
8		15 days	Tue 8/21/18	Mon 9/10/18
9	,	2 days	Tue 9/11/18	Wed 9/12/18
10	Sediment Placement on Bank	10 days	Thu 9/13/18	Wed 9/26/18
	Full Benches			
11	Sediment Placement for Channel Fill	3 days	Thu 9/27/18	Mon 10/1/18
12		1 day	Tue 10/2/18	Tue 10/2/18
12	Protection	1 uay	100/2/18	10/2/18
13		17 days	Tue 9/4/18	Wed 9/26/18
14		15 days	Tue 9/4/18	Mon 9/24/18
15		15 days	Tue 9/4/18	Mon 9/24/18
16	,	5 days	Tue 9/18/18	Mon 9/24/18
17		1 day	Tue 9/25/18	Tue 9/25/18
18	,		Wed 9/12/18	
10	-	10 days		
19	Debris Management & Disposal	1 day	Wed 9/26/18	Wed 9/26/18
20		13 days	Thu 9/27/18	Mon 10/15/18
21		12 days	Thu 9/27/18	Fri 10/12/18
22		1 day		Mon 10/15/18
23		3 days		Thu 10/18/18
23		2 days		Wed 10/17/18
24				
25	Demodilization	1 day		Thu 10/18/18
				ask
Project	t Schedule			plit 1ilestone
	Wed 4/18/18			ummary
			F	roject Summary
				nactive Task
				nactive Milestone

#### Construction – Stop Log Removal







### Construction – Sediment Dredging



#### Construction – North Bank (RDB) Reestablishment







#### Construction – Mussel Salvage







#### Construction – Causeway (Constructed Riffle)










### September Flood (Tropical Storm Gordon)







# Sept 2018 Precipitation - Inches Above Annual Mean NWS





#### Construction – Dam Demolition



#### Construction – Safety Stand Down







#### Construction – Dam Demolition



# Construction – South (LDB) Bank Reestablishment



#### Construction – North (RDB) Bank Reestablishment



#### Construction – North (RDB) Bank Reestablishment







# Levee Repairs and Stabilization






# Substantial Completion (Nov-December 2018)







## Before and After







#### Mitigation Monitoring

The annual mitigation monitoring services are expected to include the following major subtasks to be performed by ODOT (Cardno):

- Hydrology and Physical Habitat Monitoring Locations:
  - Ten (10) monitoring stations shall be established within the proposed project area, with one taken every 1,000 linear feet upstream of the dam location.
  - Data collected at each monitoring station shall include assessments of hydrology and physical habitat (Qualitative Habitat Evaluation Index [QHEI] scores).
- Biological Monitoring Locations:
  - Two (2) monitoring stations shall be established within the proposed project area, one taken immediately above the dam removal at River Mile (RM) 77.5 and the other at the U.S. Route 35/Washington Street Bridge at RM 79.5.
  - Data collected at each monitoring station shall include assessments of biology (Index of Biotic Integrity [IBI] and Modified Index of Well Being [MIwb] scores) for boat sites.





## **Mitigation Monitoring**

#### Table 3. Ohio EPA Biological Condition of GMR - Upstream of Tait Station Dam (RM 76.6)


Year	USGS RM	Narrative Location (OEPA RM <sup>1</sup> )	Lat / Long	QHEI	IBI / Miwb	ICI
1995	76.7	Ust. Tait Dam; Impounded (77.65 <sup>1,2</sup> )	39.731289 -84.199856	44.0	38 / 8.9	n/a
1995	77.2	Ust. I-75 / adj. Carillon Blvd; Impounded (78.1)	39.72930 -84.20930	42.5	42 / <mark>8.3</mark>	n/a

Summarized from "Biological and Water Quality Study of the Middle and Lower Great Miami River and Selected Tributaries, Volume 1" Ohio EPA, 1997. Red font indicates MWH. <sup>1</sup>Note: OEPA RMs presented in 1995 study are consistently off by a factor of <sup>+</sup>0.9 compared to USGS RM & FEMA FIS. <sup>2</sup>Note: The OEPA station previously identified as RM 77.1, ust. Tait Dam, is in fact located at RM 77.65 (aka USGS RM 76.7)





#### Mitigation Monitoring – QHEI v IBI v MIwb







#### Success Criteria

#### By the end of the 5-YR monitoring period,

- The restored segment of the Tait Station Dam Pool of the Great Miami River shall achieve full attainment of Warmwater Habitat (WWH) status.
- QHEI scores shall achieve a minimum average of greater than or equal to 60.0, indicative of WWH.
- Two (2) IBI scores upstream of the dam shall be no less than 45.0, indicative of WWH.
- Two (2) MI(wb) scores upstream of the dam shall be no less than 8.5, indicative of WWH.
- Project shall use only Ohio native, non-woody species to seed disturbed riparian areas along the Great Miami River. A minimum of 80% relative aerial coverage of native species, including volunteer native vegetation, shall be established.
- The restored floodplain benches inside the Miami Conservancy District levees, between the dam removal site and the upstream Interstate 75 bridge over the Great Miami River, shall have no more than 10% relative aerial coverage of invasive species.
- Post-construction monitoring shall include data to ensure the authorized activity results in net increases in aquatic resource functions and services as compared to preconstruction data.





# "For Those About to Rock" AC/DC, 1981





## Questions

Joel Thrash & Heather Schwar Cardno, Inc. (513) 489-2402 Joel.Thrash@cardno.com Heather.Schwar@cardno.com



