



### SUSTAINABLE STORMWATER MANAGEMENT IN LINEAR TRANSPORTATION PROJECTS

"Powerpoints are the peacocks of the business world: all show, no meat."

**Dwight Schrute – The Office** 





### Dunder Mifflin

Scranton, PA

# ODNR RAINWATER AND LAND DEVELOPMENT











#### April 23, 2018– New Ohio EPA Permit Issued

Ohio EPA Permit No.: OHC000005

Expires April 22, 2023

WQ<sub>v</sub> = Rv \* P \* A / 12

(Equation 1)

where:

WQv = water quality volume in acre-feet

Rv = the volumetric runoff coefficient calculated using equation 2

- P = 0.90 inch precipitation depth
- A = area draining into the BMP in acres

where i = fraction of post-construction impervious surface





#### April 23, 2018– New Ohio EPA Permit Issued

Ohio EPA Permit No.: OHC000005

Expires April 22, 2023

$$WQv = P * A * [(Rv_1*0.2) + (Rv_2 - Rv_1)] / 12$$
 (Equation 3)

where

- P = 0.90 inches
- A = area draining into the BMP in acres
- Rv<sub>1</sub> = volumetric runoff coefficient for existing conditions (current site impervious area)
- Rv<sub>2</sub> = volumetric runoff coefficient for proposed conditions (postconstruction site impervious area)





#### April 23, 2018– New Ohio EPA Permit Issued

Grassy Filter Strips removed from approved list of BMPs!

Underground Storage Extended Detention and Infiltration are now approved BMPs!

Ohio EPA Permit No.: OHC000005

Expires April 22, 2023

#### Table 4a Extended Detention Post-Construction Practices with Minimum Drain Times

Extended Detention Practices	Minimum Drain Time of WQv
Wet Extended Detention Basin <sup>1,2</sup>	24 hours
Constructed Extended Detention Wetland <sup>1,2</sup>	24 hours
Dry Extended Detention Basin <sup>1,3</sup>	48 hours
Permeable Pavement – Extended Detention <sup>1</sup>	24 hours
Underground Storage – Extended Detention <sup>1,4</sup>	24 hours
Sand & Other Media Filtration - Extended Detention <sup>1,5</sup>	24 hours

#### Table 4b Infiltration Post-Construction Practices with Maximum Drain Times

Infiltration Practices	Maximum Drain Time of WQv	
Bioretention Area/Cell <sup>1,2</sup>	24 hours	
Infiltration Basin <sup>2</sup>	24 hours	
Infiltration Trench <sup>3</sup>	48 hours	
Permeable Pavement – Infiltration <sup>3</sup>	48 hours	
Underground Storage – Infiltration <sup>3,4</sup>	48 hours	

ODOT L & D MANUAL Volume Two Drainage Design



#### ODOT Location and Design Manual (Volume Two, Drainage Design) – Section 1117 = BMP Toolbox

#### ODOT L & D Manual – Updated January 18, 2019

- Manufactured Systems
- Vegetation Based BMP
- Extended Detention
- Retention Basins
- Bioretention Cells
- Infiltration
- Constructed Wetlands
- Stream Grade Control



ODOT L & D MANUAL Volume Two Drainage Design **1117.2.1 Vegetated Filter Strips** – Roadway Projects

#### ODOT L & D Manual – Updated January 18, 2019

Table 1117-3			
Maximum Pavement Width (ft)	Slope (H:V)	Filter Strip Width (ft minimum)	
22	3:1 and flatter	15	
24	3:1 and flatter	17	
26	3:1 and flatter	18.5	
28	3:1 and flatter	20.5	
30	3:1 and flatter	22	
32	3:1 and flatter	24	
34	3:1 and flatter	25	
48	6:1 and flatter	25	



### ODOT L & D MANUAL



# **1117.2.1 Vegetated Filter Strips** – Pedestrian Facilities and Shared Use Paths

For projects that include EDA only associated with pedestrian facilities and shared use paths, with no EDA from planned roadway improvements, widths of Vegetated Filter Strips are allowed to be narrower than those in Table 1117-3. Vegetated Filter Strips are an acceptable post-construction BMP for these projects provided the following criteria are met:

- The minimum Vegetated Filter Strip width is equal to the width of the contributing impervious area.
- The maximum slope of the Vegetated Filter Strip is 3:1.
- All runoff must be sheet flow, with no concentrated flows to the Vegetated Filter Strip.











### Lakefront West

Cleveland, OH










### Lakefront West

Cleveland, OH





### Lakefront West

Cleveland, OH









#### LFW Constructed Wetland


Cleveland, OH





### LFW Dry Detention


Cleveland, OH





### Mill Creek Bikeway


Mahoning County, OH






### Towpath Stage III

Cleveland, OH









#### **Constructed Wetland**


Cleveland, OH





### **Constructed Wetland – Plant Protection**

Cleveland, OH







#### Towpath Stage III

Cleveland, OH





#### Towpath Stage III


Cleveland, OH





### B & O Corridor Wetlands

Cleveland, OH








#### **Pre-Construction Towpath Mounds**

Cleveland, OH





### Valley View Bluffs Mounds

Cleveland, OH





#### **Towpath Mounds Rendering**


Cleveland, OH





#### **Pre-Construction Towpath Mounds**

Cleveland, OH





## Total Earth Moved During Project

Cleveland, OH





# During Construction Towpath Mounds

Cleveland, OH

#### Funding







#### Michelle Johnson mjohnson@envdesigngroup.com 330.375.1390



